



Belair Park Landscape Improvements

The scheme involved the restoration of a contaminated municipal lake, within the heart of an open park in the London Borough of Dulwich.

The lake was pumped dry and the water discharged to a surface water manhole, allowing access for a long reach excavator.

Utilising a JS130 14m reach excavator the sediments were loaded into a fleet of dumpers that used a temporary timber roadway to protect the grass on route to the treatment area. This consisted of a 300mm layer of recycled timber mulch that had been collected from tree works within the borough. Sediments were blended with the mulch and formed into windrows to be periodically turned to form a compost which the Client could then use within the park.

Client

Southwark Borough Council

Works Description

Dredging Lake/Pond

Project Value

£96,580.52

Project Start Date

03/12/2003

Project Completion Date

11/04/2004

