



## PEASHOLM PARK

To alleviate flooding issues and to allow for the operation of pleasure boats at Peasholm Park, Land & Water Services was contracted by Transcore LTD to Scarborough Borough Council in early 2018 to aid the restoration works taking place by dredging the lake.

Prior to the commencement of the dredging works, a temporary causeway was installed to allow access to the lake which was drained.

### Project Delivery

- Land & Water Services' specialist amphibious excavator was deployed because of its ability to cope with low ground pressure and work on boggy ground without damaging it.
- The team put robust traffic management plans in place due to its close proximity to public highways.
- During the works, Land & Water discovered a number of 'dead' cables crossing the lake bed. The team utilised a Cable Avoidance Tool and generator to avoid any snagging or damage to machines.
- Extreme weather conditions were experienced during the project with temperature dropping to -20°C and snow which hampered haulage lorries on public highways around Scarborough.
- Members of the public would regularly visit the site to see the works progress, the Land & Water Services team were happy to inform and keep individuals up to date.

**Find us on the internet at**

**[www.land-water.co.uk](http://www.land-water.co.uk)**

Contact us on 0844 225 1958

### Project Particulars

- Around 3,750 tonnes of material was removed, loaded directly into waiting, sealed haulage waggons and transported to a licenced waste disposal site
- Client: Transcore LTD
- Project completed from February 2018 to March 2018



PROJECT  
VALUE:

**£232,517**